

The published version of the paper “Marco Breccolotti, Santino Gentile, Mauro Tommasini, Annibale Luigi Materazzi, Massimo Federico Bonfigli, Bruno Pasqualini, Valerio Colone, Marco Giancesini, Beam-column joints in continuous RC frames: Comparison between cast-in-situ and precast solutions, *Engineering Structures*, Volume 127, 2016, Pages 129-144, ISSN 0141-0296 ” is available at: <https://doi.org/10.1016/j.engstruct.2016.08.018>.

Beam-column joints in continuous RC frames: comparison between cast-in-situ and precast solutions

Marco Breccolotti^{a,*}, Santino Gentile^b, Mauro Tommasini^c, Annibale Luigi Materazzi^a, Massimo Federico Bonfigli^a, Bruno Pasqualini^b, Valerio Colone^b, Marco Giancesini^b,

^a*Department of Civil and Environmental Engineering, Perugia, Italy*

^b*Technip, Rome, Italy*

^c*MOST Monitoring and Structural Testing, Rome, Italy*

Abstract

The use of precast reinforced concrete elements is rapidly increasing since this technique has several advantages over traditional cast-in-situ structural members such as lower manufacturing time and costs and a better quality control. Nevertheless, cast-in-situ solutions intrinsically allow building moment-resisting frames, a behavior that is usually hard to achieve using precast elements. In this paper a technical solution able to offer both high strength and ductility, simplicity of construction of the prefabricated elements and ease of assembly on site is presented. The solution realizes the continuity between beam and column by means of loop splices and cast-in-place concrete with steel fibers to improve the ductility of the concrete struts

*Corresponding author

Email addresses: brec@unipg.it (Marco Breccolotti), sgentile@technip.com (Santino Gentile), tom@mostsrl.eu (Mauro Tommasini), annibale.materazzi@unipg.it (Annibale Luigi Materazzi), federico.bonfigli@strutture.unipg.it (Massimo Federico Bonfigli), bpasqualini@technip.com (Bruno Pasqualini), vcolone@technip.com (Valerio Colone), mgiancesini@technip.com (Marco Giancesini)

in the wet joint. The connection has been experimentally tested and compared to an analogous cast-in-situ one. The experimental results confirmed its good structural performances in terms of strength and ductility. Numerical investigations tuned on the basis of the experimental results allowed the improvement of the design to achieve reduced column damages for higher drift values while maintaining practically unchanged structural performances.

Keywords: Earthquake resistant structures, Precast structures, Beam-column joints, Experimental tests, FE Modeling

1. Introduction

Precast reinforced concrete techniques are increasingly replacing the cast-in-situ reinforced concrete solutions. This can be ascribed to the remarkable advantages that the prefabrication offers against traditional techniques such as the better quality of the components made in the workshop, the lower manufacturing costs, the possibility of realizing the precast components even in adverse weather conditions and the speed of construction. The cast-in-situ structures possess, however, the advantage of providing continuous frames intrinsically resistant to bending moment. This behavior should, instead, be specifically created in the prefabricated structures. Hence the choice of the right technology for the precast system is of major importance and the aim, for the designer, is to obtain a solution that is capable of obtaining the required performances in terms of load bearing capacity and ductility while minimizing construction manpower, time and costs. A number of technical solutions have been proposed for this purpose in the past, mainly focusing the attention on the load bearing capacity of the connection system. This study

17 presents a technical solution able to offer both high strength and ductility
18 in the plastic range, simplicity of construction of the prefabricated elements
19 and ease of assembly on site. The comparison of cyclic tests with imposed
20 displacements up to a drift ratio of 3.5% on a couple of external beam-column
21 joints allowed verifying the structural behavior of the prefabricated solution.
22 The results of the experimental tests showed a seismic performance of the
23 prefabricated joint very similar to that of the 'twin' cast-in-place joint. A
24 sophisticated arrangement of sensors has also allowed to analyze in detail the
25 behavior of both technological solutions. Finally, FE analyses tuned on the
26 results of the experimental tests have been used to improve the design of the
27 precast joint moving the critical region outside the connection zone without
28 reducing stiffness, strength and ductility of the joint.

29 **2. Literature review on beam-column joint in precast structures**

30 The first researches on beam-column joints have been carried out, obvi-
31 ously, with reference to cast-in-situ joints.

32 Paulay et al. [1] were among the firsts to investigate the behavior of
33 interior beam-column joints under seismic actions. They highlighted the
34 existence of two shear resisting mechanisms, one involving joint shear rein-
35 forcement and the other the concrete strut. Based on extensive experimental
36 results carried out in more than 15 years, Paulay [2] demonstrated the dis-
37 position of internal forces with diffuse diagonal cracking of the concrete core
38 and that joint shear reinforcement is necessary to sustain a diagonal com-
39 pression field rather than providing confinement to the compressed concrete
40 in the joint core.

41 Later on, similar research efforts have been provided also for precast struc-
42 tures. In this case the importance of connection detailing for structures sub-
43 jected to severe seismic action emerged since the beginning of the 90's and
44 different technical solutions have been proposed for the beam-column joints.

45 A wide joint research project called PRESSS was carried out by re-
46 searchers from the United States and Japan on the seismic design and per-
47 formance of precast concrete structural systems [3]. The objectives of this
48 program were the development of effective seismic structural systems for
49 precast buildings and the preparation of seismic design recommendations
50 for incorporation in the building codes. The attention of U.S. researchers
51 was focused on ductile connections capable of protecting the precast ele-
52 ments against inelastic deformations by means of a capacity design while the
53 Japanese program was concentrated on the strong-connection approach. The
54 results of the research project were pointed out by Priestley et al. [4].

55 Restrepo et al. [5] tested six types of subassemblages of moment resisting
56 frames located at the perimeter of buildings. Connections between the pre-
57 fabricated elements were realized at beam midspan or at the beam-to-column
58 joint region with cast-in-place concrete. The experimental results showed
59 that the connection details can be successfully designed and constructed to
60 emulate cast-in-place construction.

61 Priestley and MacRae [6] tested two ungrouted post-tensioned, precast
62 concrete beam-column joint subassemblages under cyclic reversals of inelas-
63 tic displacements to determine their seismic response. The test units were
64 designed with greatly reduced beam and joint shear reinforcement compared
65 with equivalent monolithic joints, but implementing a special spiral confine-

66 ment of the beam plastic hinge regions. Both subassemblages performed well,
67 with only minor cosmetic damage being recorded up to drift ratios of 3% or
68 more. Energy absorption of the hysteretic response, though small, was larger
69 than expected. A very low residual drift was observed after a severe earth-
70 quake. This is a characteristic of the unbonded prestressing system and is a
71 significant advantage over conventional cast-in-place reinforced concrete con-
72 struction, where very high residual drifts generally occur. It was concluded
73 that satisfactory seismic performance can be expected from well-designed
74 ungrouted precast, post-tensioned concrete frames.

75 Two full-scale beam-to-column connections of a precast concrete frame
76 were designed, following the strong-column weak-beam concept, and tested
77 by Alcocer et al. [7] under uni-directional and bi-directional cyclic loading.
78 Conventional mild steel reinforcing bars, rather than welding or special bolts,
79 were used to achieve beam continuity. Test results showed that the perfor-
80 mance of both beam-column connections was roughly 80% of that expected
81 from monolithic reinforced concrete constructions with a ductile behavior
82 due to hoop yielding. Bar pullout and strength values were nearly constant
83 up to drifts of 3.5%.

84 Korkmaz and Tankut [8] tested six 1/2.5 scaled beam-beam connection
85 subassemblies under reversed cyclic loading. The first specimen was a mono-
86 lithic one used as reference. The others were precast specimens composed of
87 a middle precast beam placed between two cantilever beams connected to the
88 columns. The connection between the precast elements region was obtained
89 by lap splicing of the top reinforcement and welding between the steel plates
90 anchored to the bottom of the middle and cantilever beams. Cast-in-situ

91 concrete on the top of the beams completed the connection. The results of
92 the tests allowed recognizing that this connection detail was not suitable for
93 seismic use. Proper modifications to obtain significant performance improve-
94 ments have been subsequently proposed and tested by the Authors.

95 A similar solution has been proposed also by Ong et al. [9] who used
96 the DfD (Design for Disassembly) method to increase material reusability in
97 the construction industry, allowing the reuse of the structural components
98 after the decommissioning of the structure instead of their demolition and
99 recycling of the resulting debris. Parastesh et al. [10] tested a new duc-
100 tile moment-resisting beam-column connection capable of providing good
101 structural integrity in the connections and reduced construction time. Their
102 solution eliminated the need for formworks and welding and minimized cast-
103 in-place concrete volume by realizing a discontinuity in the column filled by
104 the cast-in-situ concrete.

105 A wide research project, SAFECAST [11, 12], has been recently com-
106 pleted by the Joint Research Center of the European Commission. In this
107 project a full-scale three-storey precast building was subjected to a series of
108 pseudodynamic tests to evaluate the behaviour of various parameters like the
109 types of mechanical connections (traditional as well as innovative) and the
110 presence or absence of shear walls along with the framed structure.

111 *2.1. Classification of precast beam-column connections*

112 Nowadays connections between precast beams and columns can be sepa-
113 rated into three main classes: dry, hybrid and wet connections.

114 The mechanical connections made with steel elements and bolts belong to
115 the dry class. Among these connections are those tested by Vidjeapriya and

116 Jaya [13]. The Authors carried out tests on two types of simple mechanical
117 1/3 scale concrete beam-column connections realized with cleat angle with
118 1 or 2 stiffeners, subjected to reverse cyclic loading. The results of the
119 tests were then compared with the performance of a reference monolithic
120 beam-column connection. The Authors observed that ultimate load-carrying
121 capacity of the monolithic specimen was superior to that of both precast
122 specimens, while satisfactory behavior of the latter was found in terms of
123 energy dissipation and ductility.

124 Hybrid connections are those where mechanical connections and cast in
125 situ concrete are used at the same time. Hybrid connections have been tested
126 by Choi et al. [14], Ong et al. [9]. Sometimes with the same term has been
127 indicated a combination of mild steel and post-tensioning steel where the
128 mild steel was used to dissipate energy by yielding and the post-tensioning
129 steel was used to provide the shear resistance through friction developed at
130 the beam-column joint [15].

131 Wet connections are generally made up of rebar splices and cast-in-situ
132 concrete. Among the different types of rebar splices, very good mechani-
133 cal properties have been shown by loop splice connections. Several studies
134 showed that the mechanical behaviour of this type of joint, if properly de-
135 signed, can be considered similar to that of ordinary RC elements [16, 17].
136 Moreover, the use of loop splice is also frequently used in practice to establish
137 continuity between precast deck elements in steel-concrete composite bridges
138 [18].

139 Since the beginning it was recognized the usefulness of steel fibers to
140 develop ductile moment resisting wet connections designed to act as a plastic

141 hinge during earthquakes [19]. High performance fiber reinforced cement
142 composite (HPFRC) matrix was used to develop a high energy absorbing
143 joint for precast/prestressed concrete structures in seismic zones reducing the
144 amount of transverse reinforcement in the connection by using steel fibers in
145 the connection matrix [20]. Ultra high performance fiber reinforced concretes
146 (UHPFRC) were also used in conjunction with short reinforcement splice
147 lengths to develop continuity connections between precast elements to achieve
148 a safe construction process, reduced construction time and avoid the use of
149 complex reinforcing details, while maintaining high quality level [21].

150 **3. Proposed wet joint for beam-column connection**

151 The wet joint between precast beams and columns presented in this study
152 has been developed as a standard solution for pipe rack structures, commonly
153 used within worldwide oil and gas plants but it could be also adopted in other
154 continuous precast RC frames. The standard cast-in-situ solution has been
155 designed according to the ACI 318 code [22]. An example of the pipe rack
156 structures is shown in Fig. 1. They are generally composed of transversal
157 frames that are repeated along the path of the piping lines at a given spacing.
158 Considering the significant heights that can be reached by such structures
159 is clear the importance of having in seismic-prone regions a moment resist-
160 ing frame, especially in the transversal direction. The construction of such
161 facilities, which are very often located in remote regions, could turn out to
162 be far too complicated with the traditional cast-in-situ technique. A precast
163 solution would instead allow a much easier building process with reduced
164 construction time and costs.

165 Assuming initially a cast-in-situ frame, the demand of the beam critical
166 section at the beam-column intersection has been evaluated as $M_u = 1100$
167 kNm. By taking into account the capacity reduction factor for tension con-
168 trolled failure $\phi = 0.9$, the rectangular beam section 500 mm wide and 900
169 mm tall has been reinforced with 4 bars of 28 mm diameter and 2 bars with
170 25 mm diameter placed in the upper and lower sides. The nominal bending
171 strength of this section is equal to $M_n = 1233$ kNm.

172 A wide variety of solutions for precast concrete pipe racks has been de-
173 veloped along the years. All of them aimed at obtaining a monolithic frame
174 from precast pieces. Three big families of solutions can be identified:

- 175 • Cast-in-situ joints between precast beams and columns;
- 176 • Mechanical connectors between precast beams and columns;
- 177 • Monolithic precast frames.




Figure 1: Example of pipe rack for oil and gas plants.

178 For the structure under study an innovative kind of cast-in-situ joint
179 which limits the cast-in-situ volume to a minimum amount, without con-

180 nectors, scaffolding, formworks and extra material has been designed and
181 developed. In the proposed construction technique the transversal frames
182 are made up of two precast concrete columns connected with several beams
183 at different heights (Fig. 2). Each beam hosts specific elements (pipes, main-
184 tenance platforms, ...) functional to the developing plant.




Figure 2: Full-scale RC structure for pipe racks (dimensions in mm). The beam-column connection realized in 1:3 scale for the experimental tests is highlighted.

185 Fiber reinforced concrete (FRC) has been chosen to realize the wet con-
186 nection between the precast beams and columns for its favorable properties,
187 both in tension as in compression. The protruding rebars from column and
188 beams that will be embedded in the FRC casts are shown in Fig. 3. At the
189 beam ends the cross section of the prefabricated beam is gradually enlarged,
190 and thereafter divided into two prismatic elements with rectangular section,
191 called shoulders, which define a containment, the formworks, for the next
192 cast-in-situ.




Figure 3: Protruding rebars from column and beam for the wet joint connection.

193 Special attention has been paid during the design process to the strength
194 and ductility aspects but also to the ease of installation. The analyses of
195 stresses and forces inside the column joint and on the hooked rebars have

196 been carried out using well established design procedures [23, 24].

197 The assembly process and completion is shown in Fig. 4. In phase 1
198 the full height precast columns are erected. They are provided with bolted
199 brackets that will subsequently bear the precast beams. In this phase are also
200 visible the steel rebars that protrude from the column and from the beam.
201 They will be later incorporated in the final casting. In phase 2 the precast
202 beams are leaned on the brackets by means of the 2 lateral RC shoulders.
203 This is possible thanks to the shape of the solution that allows the launch of
204 the beam from above. In phase 3 the closed stirrups that were already placed
205 around the rebars protruding from the columns and the beams are disposed
206 with the correct spacing. In the final phase the connection is completed by
207 pouring the FRC in the joint using the lateral shoulders as formwork.

208 **4. Experimental program**

209 To compare the precast solution with the corresponding cast-in-situ con-
210 struction, an experimental program was carried out. Two reduced scale
211 models, the cast-in-situ reference model and the corresponding precast solu-
212 tion, have been designed and built. The test modules, i.e. the laboratory
213 specimens representing the characteristics of a typical configuration of inter-
214 secting beams and columns, have been defined according to the provision of
215 the relevant ACI standards [25, 26] for the most stressed connection of the
216 moment frame shown in Fig. 2.

217 *4.1. The specimens*

218 Both the cast-in-situ and the precast joints were realized in a 1:3 scale.
219 The adoption of this reduced scale is specifically allowed by the abovementioned




Figure 4: Assembling procedure for the beam-column connection.

220 tioned ACI standards. It has been thus assumed that no significant size
221 effects with respect to the unscaled elements are expected. The bending and
222 shear strengths of the beam critical section have been evaluated according
223 to the ACI 318 code. Their values, neglecting the strength reduction factors,
224 turned out to be $M_{n,red} = 47.2$ kNm and $V_{n,red} = 106.8$ kN. There is no risk
225 of brittle shear failure in the beam since the shear value corresponding to the
226 attainment of $M_{n,red}$, equal to 35.0 kN, is far below the shear strength $V_{n,red}$.
227 It can also be observed that the scaling procedure turned out to provide a
228 nominal bending strength $M_{n,red}$ of the scaled specimen that is very close to
229 the scaled nominal bending strength $M_n/3^3 = 45.7$ kNm.

230 The geometry of the cast-in-situ joint and the reinforcement details are
231 shown in Fig. 5. The beam section was 166.7 mm wide and 300 mm deep
232 and its longitudinal steel reinforcement consist in 2 ϕ 12 mm and 1 ϕ 14 mm
233 both in the upper and in the lower parts. The reinforcement ratio is thus
234 approximately equal to 0.8%. The 14 mm central bars are eccentric with
235 respect to the cross section axis to avoid the interference with the central
236 bars of the column. Two ϕ 8 mm bars have been located in the center of the
237 lateral sides of the section in order to better restraint the stirrups. These
238 latter consisted in ϕ 6 mm bars with a spacing of 110 mm near the hinged
239 connections and the joint, and with a spacing of 250 mm in the central
240 portion where the shear forces are lower. The column had a cross-section
241 266.7 mm wide and 300 mm deep and its reinforcement is made up of 4 ϕ 16
242 mm along the edges of the section and 4 ϕ 14 mm in the middle of the sides.
243 The stirrups had a spacing of 60 mm near the hinged connections where
244 a concentrated load is applied, while in the remaining parts the spacing is

Concrete	Cement (kg/m^3)	W/C ratio	Sand (kg/m^3)	Gravel (kg/m^3)	Hyperplasticizer (l/m^3)	Fibers (kg/m^3)
Cast in situ	380	0.395	940	850	3.8	0
Precast	380	0.395	940	850	4.2	0
FRC	640	0.300	583	800	6.4	39

Table 1: Concrete mix designs used for the tested specimens.

245 approximately equal to 243 mm. Additional bars were located around the
 246 connection points between the RC elements and the mockup structure in
 247 order to prevent a local collapse of the sample outside the area of the joint
 248 connection. The precast joint has the same geometry and reinforcement of
 249 the cast-in-situ one, except for the area where the connection between the
 250 beam and the column is realized (see Fig. 6). Here the beam widened up
 251 to 233.3 mm, realizing an U-shaped connection that was supported by the
 252 RC bracket bolted to the column. This wider dimension does not affect
 253 the bearing capacity of the beam in the critical zone since the lateral thin
 254 concrete panels only serve as formworks for the FRC cast and there is no
 255 significant transfer of forces between these elements. Furthermore, as visible
 256 in the upper view of Fig. 6, a 17 mm gap prevents any contact between the
 257 lateral thin concrete panels and the column. The gap has been filled with
 258 deformable caulk prior to the casting of the FRC to avoid the transmission
 259 of significant stresses to the lateral RC brackets. Longitudinal ring-shaped
 260 bars come out from the beam and from the column in this region. When the
 261 placement of the beam on the bracket was completed, the continuity between
 262 the two elements was realized by means of a FRC cast that filled the U slot.

263 Three different types of concretes, two for the cast-in-situ and precast
 264 RC elements and one for the wet connection, have been used for the con-

Concrete	Compressive strength	
	53 hours (MPa)	125 days (MPa)
Cast in situ	8.6	39.2
Precast	6.4	35.8
FRC	17.0	69.4

Table 2: Concrete compressive strength of the tested specimens.

Diameter ϕ (mm)	Yielding stress (MPa)	Tensile strength (MPa)	Yielding strain ($\mu\epsilon$)
6		443	
12	453	584	2199
14	466	602	2262

Table 3: Mechanical properties of the reinforcing steels.

265 construction of the test modules. Steel fiber reinforced concrete has been chosen
266 for the concrete of the wet-joint to increase the ductility properties of the
267 compressed strut in the connection. The mix designs of the three concretes
268 are shown in Tab. 1 while the compressive strengths at 53 hours and at
269 125 days of the same mixes are listed in Tab. 2. The concrete compres-
270 sive strength of the cast-in-situ, precast and steel fiber reinforced concretes
271 at 125 days have been evaluated a few days before the testing of the two
272 specimens. In the tables it can be noticed that the concretes used for the
273 cast-in-situ and the precast elements have almost the same composition and
274 achieved approximately the same compressive strength. The volume fraction
275 of the fiber has been chosen taking into account the specific feature of the
276 proposed connection. Obviously, the higher is the fiber content, the higher
277 is the increase in strength and ductility but, on the other hand, high fiber
278 content can lead to a significant reduction in the concrete workability. For
279 the proposed beam-column connection the tensile strength and ductility of




Figure 5: Geometrical dimension (mm) and reinforcement layout of the cast-in-situ specimen. Upper view, side view and cross-sections.

280 the cast-in-place concrete do not play a major role. In fact, at the inter-
 281 face between the cast-in-place concrete and the precast elements only a weak
 282 tensile strength (adhesion) can develop and, thus, in these regions cracks
 283 are primarily expected to occur. For this reason no significant increases in
 284 the tensile strength and in the toughness are necessary for the cast-in-situ




Figure 6: Geometrical dimensions (mm) and reinforcement layout of the precast specimen. Upper view, side view and cross-sections.

285 concrete. Conversely, good strength and good ductility properties are re-
 286 quired for the compression stress-strain relationship in order to improve the
 287 behavior of the concrete strut inside the connection region. Considering the
 288 above mentioned reduction in the concrete workability and considering also
 289 the data reported in the works by Taerwe and Van Gysel [27], Neves and

290 Fernandes de Almeida [28] and Marar et al. [29], a fiber volume fraction
291 of 0.5% has been judged suitable for the cast-in-place concrete. Among the
292 different types of fibers, the steel ones have been selected for their ability to
293 improve the flexural toughness and for their flexural fatigue endurance [30].
294 Commercially available steel fibers were used in the FRC. They are char-
295 acterized by a length of 33 mm, a diameter of 0.55 mm, a tensile strength
296 higher than 1200 MPa and double-end hooks to ensure a proper anchorage
297 in the concrete. The content of fibers in the FRC was equal to 39 kg/m³,
298 resulting in a volumetric fraction approximately equal to 0.5%. B450C steel
299 rebars have been used for every reinforcement. The mechanical properties of
300 the steel rebars are listed in the Table 3.

301 Fig. 7 shows the reinforcement and the formwork of the cast-in-situ so-
302 lution just before the concreting, whereas Fig. 8 shows the precast column
303 just after the concreting.

304 *4.2. Test setup*

305 In order to correctly execute the experimental tests, an ad-hoc setup was
306 designed (Fig. 9) and built (Fig. 10). The whole apparatus was installed
307 inside a test chamber, delimited by a RC reaction wall. The column was
308 supported by a steel cylinder whose function was that of providing the ver-
309 tical reaction force without notable horizontal components. The horizontal
310 reaction was instead provided by a stiff steel frame anchored on one side to
311 the rigid RC wall, and on the other side to the lower part of the column using
312 a pinned connection, thus allowing rotation to occur. On the upper part of
313 the column an hydraulic jack attached to the reaction wall was connected
314 to the column using a pinned connection. The jack provided the horizontal



Figure 7: Reinforcement and formwork of the cast-in-situ specimen.



Figure 8: Precast column just after the concreting.

315 force that was used to control the column drift. The beam was connected by
316 means of a pinned restraint to a steel frame. This latter was linked to a rigid
317 steel base that was integral with the floor using a bolted connection. The
318 steel frame applied a restraint to the beam only in the vertical direction al-
319 lowing at the same time the horizontal movement of the beam itself (see Fig.
320 9). No notable horizontal restraining force was thus applied to the end of the
321 beam. A second hydraulic ram actuator placed on the top of the column was
322 used to apply a suitable compressive force to the column. The value of this
323 force corresponds to the axial load induced in the column by the permanent
324 loads in the overlying portion of the structure of the pipe rack (see Fig. 2)
325 reduced by a scale factor of 9 to take into account the scale of the specimen.
326 The reaction exerted by the jack was transmitted to the ground by means of
327 two threaded steel rods.

328 This hydraulic jack was actuated by a manually operated hydraulic pump
329 to impose the predetermined compressive force. In order to minimize the vari-
330 ations in trim during the execution of the tests, it was used a hemispherical
331 head interposed between the vertical actuator and the top of the column. A
332 load cell was installed between the actuator and the column to control and
333 store the time history of the vertical load.

334 *4.3. Sensors*

335 The relative horizontal displacement between the bottom hinge and the
336 top hinge of the column was monitored by means of two displacement sensors
337 (Fig. 9): a wire transducer (WT) linked to the ground was applied on the
338 top of the column at the same height of the hydraulic jack, while a linear
339 variable displacement transducer (LVDT) was applied on the bottom hinge.




Figure 9: Schematic representation of the experimental test setup: rear view (left), side view (center) and front view (right).



Figure 10: Picture of the experimental setup before the beginning of precast joint test.

340 The difference between the two values defines the actual applied drift. A
 341 pressure transducer was used to measure the pressure in the hydraulic jack.
 342 Several sensors, shown in Fig. 11, were also applied to the experimental

343 setup to monitor the joint behavior and to obtain a careful evaluation of the
344 stresses in the concrete and in the reinforcing steel. Vibrating wire strain
345 gauges (VWSG) were embedded into the concrete in the upper and in the
346 lower areas of the beam section nearby the joint, both in the cast-in-situ and
347 in the precast joint. The sensors have been placed just outside the critical
348 region to avoid any drawback during the execution of the tests. Similarly,
349 VWSGs were also fixed to the lower and upper steel bars of the beam (Fig.
350 12a). In addition, further VWSGs were also fixed in the precast joint to the
351 steel rebars inside the column (Fig. 12b) to verify the actual transmission
352 of stress from the reinforcing bars of the beam to those integral with the
353 precast column. The choice of the vibrating wire strain sensors (compared
354 to resistive strain gauges) has been made mainly considering the need of
355 measuring the deformation of the concrete over a significantly long distance,
356 compared to the size of the aggregates.

357 Additional potentiometric linear variable displacement transducers (PDT)
358 were also applied to the joint to measure its overall deformation. One trans-
359 ducer was located on the upper part of beam section to detect the horizontal
360 relative displacements between the upper outer layer of concrete and the
361 outer concrete of the column. Similarly, another transducer was applied on
362 the bottom part of the beam section. Finally two transducers were placed in
363 a X-shaped configuration connecting the lateral concrete surface of the beam
364 and the lateral surface of the column. The combination of the data coming
365 from the two couples of PDT, each composed by one inclined PDT and by
366 the opposite horizontal one, allowed verifying the shear deformation occurred
367 in the beam critical zone during the tests that proved to be negligible. Sig-

Instrument	Measure	Type
Embedment vibrating wire strain gauges - VWGSe	Concrete strain	GV-4200: 150 mm gauge length, 3000 μ strain (± 1500), Linearity $< 0.5\%$, Internal thermistor (-20/+80 C)
Arc weldable vibrating wire strain gauges - VWGSaw	Rebar strain	GV-4200AW: 150 mm gauge length, 3300 μ strain, Linearity $< 0.5\%$, Internal thermistor (-30/+80 C)
Linear variable potentiometric displacement transducers - PDT	Displacement between column and beam	Gefran PZ34-A-150: 150 mm range, Linearity 0.05%, Power supply: 12 Vcc
Linear variable differential transformer displacement transducers - LVDT	Displacement between ground and bottom of the column	HBM WA: 100 mm range, Linearity $\pm 0.01\%$, Power supply: 12 Vcc
Wire rotative potentiometric displacement transducers - WT	Displacement between ground and top of the column	Celesco PT101-0020-111-5110: 500 mm range, Linearity 0.07%, Power supply: 12 Vcc

Table 4: Instruments installed on specimens.

368 nals from the sensors were recorded using a double system of measurement
369 based on two data acquisition units synchronized together by a digital line
370 and configured for a scan data rate of 1 Hz.

371 4.4. Testing procedure

372 Joint specimens were subjected to a sequence of displacement-controlled
373 cycles representative of the drifts expected under earthquake motions and
374 defined in accordance to the ACI standards [25, 26]. The drift sequence,
375 shown in Fig. 13, has been established complying with the following rules:

- 376 • the initial drift ratio must be within the essentially linear elastic re-
377 sponse range;
- 378 • subsequent drift ratios must be not less than one and one-quarter times,
379 and not more than one and one-half times the previous drift ratio;






Figure 11: Schematic representation of the sensors.

- 380 • three fully reversed cycles must be applied for each drift ratio value.
- 381 Testing have been continued with gradually increasing drift ratio until it
- 382 reached a value of 4.33%.



(a)



(b)

Figure 12: VWSGs fixed to the reinforcing steel: (a) in the precast beam and (b) to the reinforcing steel in the precast column.

383 **5. Tests results**

384 In the present chapter are presented and analyzed the results of the ex-
385 perimental investigations on the cast-in-situ and precast specimens. Being
386 the objective of this study that of verifying if the precast joint fulfilled the
387 provision of ACI Standards, the tests have been terminated after completing




Figure 13: Test sequence of the displacement controlled cycles.

388 the 4.33% drift cycle. Thus, after having verified that the third complete
 389 cycle at drift ratio of 3.5% presented a peak force not less than 0.75 times
 390 the maximum applied force for the same direction, just one more drift ratio
 391 at 4.33% has been investigated.

392 Before going to the main experimental results it is helpful to understand
 393 how the vertical force applied on the top of the specimen varied during the
 394 experimental test for the imposed horizontal displacement. From Fig. 14 it
 395 can be noted that, starting from the initial value of 155 kN (scaled permanent
 396 axial load due to the overlying portion of the structure), the force increases
 397 as the imposed displacement increases. This behavior corresponds to that
 398 occurring in the real structure during an earthquake excitation.

399 The main findings on the behavior of the precast joint in comparison
 400 with that of the cast-in-situ joint can be drawn observing the force vs. drift




Figure 14: Time history of the axial force applied on the top of the specimen during the experimental test.

401 responses recorded during the two experimental tests, shown in Fig. 15.
 402 First of all, it can be noted that the drift-load relationship of the precast
 403 specimen is very similar to that obtained by other researchers for analogous
 404 connections [10, 31] with a stable ductile behavior for drift values in the
 405 range 1.5%-4.3%. The summary data of the the tests are listed in the Table
 406 5. It is evident that the strength and the ductility of the two specimens
 407 are very similar. Indeed, the precast joint behavior (dashed lines) appears
 408 to be even more resistant than the cast-in-situ joint (solid lines) without
 409 appreciable changes to the ductility of the joint. In fact, the cast-in-situ
 410 specimen started yielding under positive drift values with an applied load of
 411 roughly 40 kN while the precast joint yielded as a result of the application
 412 of a 50 kN horizontal force. A similar observation with slightly higher force
 413 values can also be done for negative drift values. The first value is in very

Specimen	Positive displacement		Negative displacement	
	Max load (kN)	Displ. (mm)	Max load (kN)	Displ. (mm)
Cast-in-situ	50.0	51.0	-59.5	-51.2
Precast	58.1	59.3	-69.7	-61.4

Table 5: Summary of the test results.

414 good agreement with that resulting from the calculation in correspondence
415 of the yielding of the beam steel rebars equal to 35.0 kN obtained as the ratio
416 between the nominal bending strength $M_{n,red} = 47.2$ kNm and the distance
417 $L/2 = 1.35$ m between the critical section and the beam support. The second
418 one is higher than that expected for the higher compressive strength of the
419 FRC.





Figure 15: Force vs drift response of the cast-in-situ (solid curve) and the precast (dashed curve) specimens.

420 The crack patterns observed at the end of the tests for the cast-in-situ
421 and the precast joints are shown in Fig. 16. The cracking pattern inside the
422 joint region for both cases was similar to that obtained for this type of exte-
423 rior beam-column connections by other researchers [32, 33, 10]. In particular,
424 cracks with an inclination of roughly $\pm 45^\circ$ on the horizontal have been de-
425 tected inside the joint region while horizontal cracks have been detected just
426 above and just below the joint region. For the monolithic connection a dif-
427 fused cracking is present in the critical zone of the beam with very few cracks
428 in the column. A main crack, located in the beam at about 100 mm from
429 the column face, is also visible in the picture. A severe concrete spalling also
430 occurred in the top concrete cover. The precast connection shows an appar-
431 ent reduced state of cracking in the critical zone but also in this case a main
432 crack, located at roughly 50 mm from the column face, occurred during the
433 tests. Nevertheless, the real state of the cracking occurred in the FRC matrix
434 is not visible since it is hidden by the lateral precast concrete plates used as
435 formworks. The presence of the crack at the beam-column connection can
436 be inferred by looking at Fig. 18b and in particular to the data recorded by
437 the sensors LVDTH1 and LVDTH2. In fact it can be noted that the readings
438 of these sensors are not symmetric with positive values (lengthening) much
439 greater than the negative ones (shortening). The difference between these
440 two values is representative of the main crack amplitude.

441 The sensors embedded in the specimens allowed to carry out an in-depth
442 analysis of the stress state in the materials. Among the available data, the
443 most interesting ones turned out to be those provided by the VWSG con-
444 nected to the upper rebars. These data are shown in Fig. 17. The strains



(a)



(b)

Figure 16: Crack patterns at the end of the tests for: (a) the cast-in-situ and (b) the precast joints.


445 recorded by the sensors placed inside the cast-in-situ and the precast beams
446 gradually increased up to a drift ratio of 2.4% corresponding to a top dis-

447 placement of ± 36 mm. Afterward the steel strain has maintained maximum
448 deformation values practically constant up to the end of the tests. This
449 behavior can be ascribed to the yielding of the reinforcing bars within the
450 critical zone. Nevertheless it should be emphasized that the maximum strain
451 value recorded in the cast-in-situ joint is slightly higher (approx $2250 \mu\epsilon$)
452 than that observed in the precast joint (approx $1750 \mu\epsilon$). Most likely this
453 occurred for the overlapping of the rebars in the precast specimen that pre-
454 vented the yielding of the rebars in the area where they are fully overlapped
455 and caused the yielding of the steel rebars just outside this area. A confir-
456 mation to this thesis has been obtained observing the data gathered from
457 the VWSG placed inside the column, also plotted in the same figure. Values
458 well above the yielding deformation, shown in the Table 3, have been in fact
459 recorded by this sensor. For the precast specimen it can thus be noted that
460 the zone where the yielding of the steel rebars take place is just between
461 the end of the loop coming from the beam and the lateral side of the col-
462 umn, as confirmed by the above mentioned crack pattern. This finding also
463 demonstrates the ability of the proposed connection system to transmit the
464 bending moment to the column. Nevertheless, the yielding of the steel re-
465 bars can produce tensile cracks inside the column resulting in a not negligible
466 damage of concrete. The use of protruding reinforcing bars with diameter
467 larger than those of the connected beam would avoid this excessive concrete
468 damage inside the joint, inducing the steel yielding to occur only inside the
469 beam as will be shown in the next section by means of FE analysis.


470 The influence of the shear deformation on the total deformation of the
471 beam critical region can be observed by looking at the data recorded by the

472 PDTs during the experimental tests shown in Fig. 18. The mean transversal
473 displacement of the section placed at 360 mm from the column face can be
474 obtained by using trigonometry equations reported in the enclosed Appendix.
475 This value is made up of the flexural and the shear deformation of the beam
476 critical zone. The contribution of the shear deformation can be extracted
477 from the data recorded by the PDTs according to the method proposed by
478 Massone and Wallace [34]. From the comparison of the two values shown
479 in Fig. 19 it can be deduced that the shear deformation is negligible in the
480 elastic range and for small amount of the damage in the specimens. The
481 effect produced by the occurrence of the main crack is, instead, relevant as
482 can be deduced by comparing the graphs of Figs. 18 and 19. It can be,
483 in fact, observed that at the same time at which the elongation recorded by
484 LVDTs starts increasing rapidly (due to the formation of the main crack) the
485 shear deformation also starts increasing. This happens after roughly 5800 sec
486 for the cast-in-situ specimen (Fig. 18a and Fig. 19a) and around 4600 sec
487 for the precast specimen (Fig. 18b and Fig. 19b). It can, thus, be deduced
488 that the severe cracking reduced in a consistent way the shear stiffness of the
489 joint.

490 To summarize, the progressive damage and collapse observed in the two
491 types of joint can be judged very similar with the only difference that in the
492 cast-in-situ joint the spalling of the upper concrete cover, probably due to
493 the lower concrete strength and to the absence of the steel fibers with respect
494 to FRC, prevented the attainment of higher lateral forces.



(a)




(b)


Figure 17: Strains recorded in the upper rebars: (a) in the cast-in-situ and (b) in the precast joints.

495 **6. Improvement of the connection system**

496 The experimental tests carried out on the precast specimen allowed to
 497 validate the connection system between the beam and the pillar demonstrat-




(a)




(b)

Figure 18: Elongation recorded by the LVDTs: (a) in the cast-in-situ and (b) in the precast joints.



(a)



(b)

Figure 19: Total (solid line) and shear (dashed line) transversal deformation: (a) in the cast-in-situ and (b) in the precast joints.

498 ing that the prefabricated solution has a behavior quite similar, if not better,
 499 than that of the cast-in-situ solution. Nevertheless, the measurements car-
 500 ried out with the VWSGs connected to the reinforcing bars of the beam
 501 showed a significant steel yielding in correspondence of the rebars portion
 502 in the joint inside the column. As a consequence, a not negligible concrete
 503 cracking inside the column (see Fig. 16b) was produced, a type of damage
 504 that should generally be avoided.

505 The connection system between the precast beam and column easily allow
 506 to overcome this drawback by simply adopting protruding bars from the
 507 beam having a smaller diameter than those protruding from the column.
 508 This modification will cause the shift of the steel yielding zone inside the
 509 beam, just outside the area of overlap of the rebars (section with M_{Rd2} in
 510 Fig. 20). In fact, the presence of overlapping rebars neglect the steel yielding
 511 in this area. The reduction in the bar diameter depends on the extent of the
 512 overlapping length l_1 and can be estimated by the following equation:

$$\gamma_{Rd} \cdot M_{Rd2} \leq M_{Rd1} \cdot \frac{L - 2l_1}{L} - \Delta M_{Ed,1,2} \quad (1)$$

513 where M_{Rd1} and M_{Rd2} are the resisting moments of the sections just
 514 outside the column and just outside the overlapping area, L is the length of
 515 the beam, γ_{Rd} is an overstrength factor to take into account the uncertainty
 516 on the resistances design values in the estimation of the capacity design action
 517 effects, as done for instance by EN 1998 [35] and $\Delta M_{Ed,1,2}$ is the difference
 518 between the bending moment in the sections 1 and 2 (see Fig. 20) produced
 519 by the vertical loads. Moreover, the following design controls must be carried
 520 out to ensure a correct hierarchy of resistances avoiding brittle shear failures

521 in the beam:

$$V_{Rd1} \geq (g + \psi_2 q) \cdot \frac{L}{2} + \gamma_{Rd} \cdot \frac{2M_{Rd1}}{L} \quad (2)$$

$$V_{Rd2} \geq (g + \psi_2 q) \cdot \frac{L - 2l_1}{2} + \gamma_{Rd} \cdot \frac{2M_{Rd2}}{L - 2l_1} \quad (3)$$

522 where V_{Rd1} and V_{Rd2} are the shear strength of the sections just outside the
 523 column and just outside the overlapping area, g is the self weight load and
 524 $\psi_2 q$ is the variable load acting on the beam in the seismic load combination.

525 To avoid failure inside the beam-column joint it must be also checked
 526 that the diagonal compression force induced in the joint by the diagonal
 527 strut mechanism does not exceed the compressive strength of the concrete.
 528 For instance, EN 1998 [35] assumes satisfied this clause for exterior beam-
 529 column joints if the following inequality holds:

$$V_{jRd} \geq V_{jEd} \quad (4)$$

530 having indicated with

$$V_{jRd} = 0.8\eta \cdot f_{cd} \sqrt{1 - \frac{\nu_d}{\eta}} \cdot b_j \cdot h_{jc} \quad (5)$$

531 where $\eta = 0.6(1 - f_{ck}/250)$, h_{jc} is the distance between the extreme layers
 532 of column reinforcement, b_j is the effective joint width, ν_d is the normalized
 533 axial force in the column above the joint, f_{ck} is the concrete characteristic
 534 strength given in MPa and with V_{jEd} the maximum horizontal shear that
 535 can act on the core of the joint. This latter can be calculate for an exterior
 536 beam-column joint as follow:

$$V_{jEd} = \gamma_{Rd} \cdot A_{s1} \cdot f_{yd} - V_C \quad (6)$$

537 with A_{s1} the area of the beam top reinforcement, V_C the shear force in
538 the column above the joint and γ_{Rd} the already mentioned factor to account
539 for steel overstrength.

540 For instance, for the precast joint tested in this work Eq. 4 turned out to
541 be:

$$V_{jEd} = 248.4kN < 355.7kN = V_{jRd} \quad (7)$$

542 having assumed $\gamma_{Rd} = 1.20$, $A_{s1} = 380mm^2$, $f_{yd} = 391.3MPa$, $V_C =$
543 $-70kN$, $f_{ck} = MPa$, $b_j = 167mm$, $h_j = 250mm$, $N_c = 210kN$.

544 Finally, the column has to be over-designed with respect to the beam
545 flexural strength M_{Rd1} . At the same time, the dimension of the FRC cast has
546 been shortened from 323 mm to 214 mm to reduce the construction costs and
547 to simplify the building. By doing so, the width of the joint became smaller
548 than that recommended by the relevant *fib* standard [24] for loop connections
549 in wet joints with conventional concretes. However, it has already been shown
550 that this reduction can be achieved by using FRC [36]. According to Eq. 1
551 this reduction also allows to increase the bending strength M_{Rd2} that should
552 be provided by the rebars protruding from the beam. Finally, the beam
553 longitudinal steel reinforcement of the original joint (2 ϕ 12 mm and 1 ϕ 14
554 mm rebars, see Fig. 6) has been reduced based on the same equation to 2 ϕ
555 12 mm and 1 ϕ 10 mm rebars.

556 Nevertheless, the overlapping can not be too small to provide a suitable
557 force transfer, even if each bar has an hook shape and can thus be considered
558 as self-anchored. The improvement of the structural behavior achievable with
559 this solution has been tested by means of nonlinear finite element analysis
560 described in the following paragraphs.




Figure 20: Geometrical dimensions and reference bending and shear strengths of the precast beam.

561 6.1. Numerical models

562 Two different models, shown in Fig. 21, have been implemented with the
 563 general purpose commercial finite element software ABAQUS for the tested
 564 specimen and for the modified configuration. 8-node brick finite elements
 565 have been used to model the concretes while the reinforcement bars were
 566 modeled by 2-noded truss elements.

567 The mechanical model adopted for the concrete is the "Concrete Damaged
 568 Plasticity" (CDP). This model is suitable for analyzing the inelastic behavior
 569 of concrete under monotonic, cyclic or dynamic loading. It also allows eval-
 570 uating the degradation of material stiffness during cyclic loadings by means
 571 of damage parameters. The main parameters defined to model the concrete
 572 behaviour were density, tangent elastic stiffness and CDP model parameters.
 573 Among these latter the most important ones were the two stress-strain inelas-
 574 tic constitutive laws for concrete subject respectively to monotonic tension
 575 and compression. Additional parameters specified for the CDP model are

576 dilation angle Ψ , eccentricity ε , ratio σ_{b0}/σ_{c0} between the initial equibiax-
577 ial compressive yield stress to initial uniaxial compressive yield stress and
578 parameter K_c (ratio of the second stress invariant on the tensile meridian
579 to that on the compressive meridian). These latter parameters have been
580 assumed equal to the reference values for typical concretes [37]. Their values
581 are given in Table 6. No viscoplastic regularization has been implemented
582 in the model as well as no compressive and tensile damage variables were
583 specified since no cyclic loading has been imposed to the concrete.

584 The compression non-linear stress-strain curves proposed by the *fib* Model
585 Code 2010 [38] have been used for both the concrete of the precast elements
586 and for the FRC:

$$\sigma_c = f_{cm} \cdot \frac{k \cdot \eta - \eta^2}{1 + (k - 2) \cdot \eta} \quad (8)$$

587 where $\eta = \epsilon_c/\epsilon_{c1}$, $k = E_{ci}/E_{c1}$, ϵ_c is the concrete strain, ϵ_{c1} is the strain
588 at maximum compressive stress, E_{ci} is the modulus of elasticity at concrete
589 age of 28 days, E_{c1} is the secant modulus from the origin to the peak com-
590 pressive stress and k is the plasticity number provided by the Model Code.
591 For the tensile non-linear stress-strain curve of the FRC, based on the data
592 found in the literature [39] and considering the low volume fraction of the
593 steel fibers, a strain-softening behaviour has been assumed for the FRC. The
594 tensile strain softening curves shown in Fig. 22(a) have been deduced from
595 the experimental tests carried out on similar concretes by Yang et al. [40].

596 The steel reinforcements have been modeled using an elasto-plastic con-
597 stitutive law with strain hardening. The stress-strain relationships for these
598 materials are shown in Fig. 22(b).

599 The interaction between rebars and concrete has been implemented by

600 modeling the reinforcements as embedded elements hosted in the concrete
601 solid parts. This constraint eliminates the degrees of freedom of the rebar
602 mesh nodes and forces these latter to displace by interpolating the neigh-
603 bouring concrete mesh nodal displacements. Low friction and weak adhesion
604 has been used to simulate the contact between the two type of concretes. An
605 increasing displacement has been imposed to the top of the RC column and
606 suitable boundary conditions have been applied to simulate the experimental
607 test. For the purpose of this analysis the cumulative damage provided by the
608 cyclic loading has been neglected.






Figure 21: FE models of the original precast joint (left) and of the modified precast joint (right) with dimensions of connection zone in mm.

609 6.2. Results of the FE simulations

610 The results of the FE simulations can be summarized by considering
611 the relationship between the force applied to the RC column and its dis-
612 placement. It must be first observed that a quite good agreement has been
613 obtained between the curve of the experimental tests and that of the equiv-
614 alent FE model, as observable in Fig. 23, thus validating the numerical



(a)



(b)

Figure 22: Stress-strain relationships for: (a) the concretes and (b) the reinforcing steel.

615 model. In the same figure is also shown the force-displacement curve for the
 616 joint with the modified configuration. It can be noticed that the behavior is
 617 very similar to that of the original configuration. The improvements of the
 618 structural behavior are, however, visible in Fig. 24 where is represented the
 619 stress state of the rebars in the two configurations. As visible, in the original

Material parameters		
Parameter	Precast concrete	FRC
ρ (Kg/m ³)	2300	2300
E_0 (MPa)	32308	39441
ν	0.1	0.1
ε	0.1	0.1
Ψ	35°	35°
K_c	2/3	2/3
σ_{b0}/σ_{c0}	1.16	1.16
σ_{cu} (MPa)	36	70
ϵ_u	0.0045	0.004
σ_{tu} (MPa)	3.32	7
d_c	0	0
d_t	0	0
w_c	0	0
w_t	0	0

Table 6: Assumed values for the CDP parameters of the precast concrete and FRC.

620 configuration the yielding of the rebars, indicated with red color, takes place
621 primarily within the node in the pillar while it moved into the beam out-
622 side the area of overlapping in the modified configuration. The persistence
623 in the elastic range of the reinforcing bars embedded in the pillar and the
624 presence of damage only inside the beam also allows for the realization of
625 easier repairs in the case of severe earthquakes. Nevertheless, it has to be
626 highlighted that the shortening of the splice length produces an increase in
627 the compression principal stresses in the FRC inside the overlapping region.
628 In fact the maximum concrete compressive stress inside the loop splice is
629 approximately equal to 8 MPa in the original precast joint, as shown in Fig.
630 25, and becomes roughly 13 MPa in the modified precast joint. Whereas this
631 value is still acceptable for the mechanical properties of the FRC, further
632 experimental investigations should be performed for real design cases.






Figure 23: Comparison between the experimental force-displacement envelope and the force-displacement curves of the two FE models.

633 7. Conclusions

634 A technique to realize beam-column joints in precast RC frames has been
 635 presented in this paper. It is based on prefabricated beams and columns
 636 with protruding bars that are connected in-situ by means of a concrete wet
 637 joint with steel fibers to moderately increase the ductility properties of the
 638 compressed struts in the joint. Experimental tests allowed comparing the
 639 structural behavior of a beam-column sub-assembly realized with this tech-
 640 nique to that of an equivalent cast-in-situ beam-column joint. The results
 641 of these tests showed that the two solutions exhibited very similar structural
 642 behaviors, with the proposed solution achieving a slightly greater strength
 643 and stiffness than those of the cast-in-situ solution without relevant modifi-
 644 cations to the joint ductility. Numerical simulations have been subsequently
 645 performed to improve the damaging mechanism of the precast beam-column
 646 connection. In detail, the arrangement of the reinforcing steel has been up-




(a)




(b)

Figure 24: Stress state of the rebars in the FE models: (a) original precast joint and (b) modified precast joint. Yielded rebars are shown in red. Values in kPa.

647 dated in order to avoid the yielding of the steel inside the column and to
 648 move the plastic zone inside the beam. The so-obtained damage pattern has
 649 been thus concentrated in the beam, allowing for easier restoration works



(a)



(b)

Figure 25: Minimum principal stresses in the FE models: (a) original precast joint and (b) modified precast joint (Values in kPa, Loop splices indicated with dashed lines).

650 that should be carried out after a severe earthquake.

651 **Acknowledgments**

652 This research was supported by the jointventure ETILENO XXI Contrac-
 653 tors SAPI de CV between the firms Technip, Odebrecht and Icaflur. The
 654 authors would like to extend their sincere thank to Mr Ascenzo Burzichelli
 655 and Mr Paolo Lopriore, respectively Project Director and Head of Engineer-
 656 ing Department at Technip Italy s.p.a., for their invaluable assistance.

657 **Appendix**

658 With the symbols shown in Fig. 26, the following angles have been cal-
 659 culated:

$$\alpha_1 = \arccos \left[\frac{(b_1 + \Delta b_1)^2 + c^2 - (d_1 + \Delta d_1)^2}{2c(b_1 + \Delta b_1)} \right] \quad (9)$$

$$\alpha_2 = \arccos \left[\frac{(b_2 + \Delta b_2)^2 + c^2 - (d_2 + \Delta d_2)^2}{2c(b_2 + \Delta b_2)} \right] \quad (10)$$

660 where b_1 , b_2 , c , d_1 and d_2 are the dimension of the initial LVDT configu-
 661 ration and Δb_1 , Δb_2 , Δd_1 and Δd_2 are the readings of the LVDT during the
 662 tests. Referring to the coordinate system of the above mentioned figure, the
 663 transversal coordinates of points 1 and 2 can be calculated as:

$$y_1 = \frac{c}{2} - (b_1 + \Delta b_1) \cdot \cos(\alpha_1) \quad (11)$$

$$y_2 = -\frac{c}{2} + (b_2 + \Delta b_2) \cdot \cos(\alpha_2) \quad (12)$$

664 The transversal displacement of the mean point of segment $\overline{12}$ is thus
 665 equal to:

$$y_m = \frac{y_1 + y_2}{2} \quad (13)$$

666 According to Massone and Wallace [34] and assuming small deformations
 667 inside the node region the shear displacement can be calculated as follows:

$$y_{m,s} = \frac{\sqrt{(d_1 + \Delta d_1)^2 - c^2} - \sqrt{(d_2 + \Delta d_2)^2 - c^2}}{2} + \left(\frac{1}{2} - \alpha \right) \cdot l \cdot \cos \left(\frac{\alpha_1 + 180 - \alpha_2}{2} \right) \quad (14)$$

668 with α equal to 0.67.




Figure 26: LVDT lengths in the initial (top) and deformed (bottom) configurations.

669 **References**

670 [1] T. Paulay, R. Park, M. Priestley, Reinforced concrete beam-column
 671 joints under seismic actions., J Am Concr Inst 75 (11) (1978) 585–593.

672 [2] T. Paulay, Equilibrium criteria for reinforced concrete beam-column

- 673 joints, ACI Structural Journal 86 (6) (1989) 635–643.
- 674 [3] M. Priestley, Overview of presss research program, PCI Journal 36 (4)
675 (1991) 50–57.
- 676 [4] M. Priestley, S. Sritharan, J. Conley, S. Pampanin, Preliminary results
677 and conclusions from the presss five-story precast concrete test building,
678 PCI Journal 44 (6) (1999) 42–67.
- 679 [5] J. I. Restrepo, R. Park, A. H. Buchanan, Test on connections of earth-
680 quake resisting precast reinforced concrete perimeter frames of buildings,
681 PCI Journal 40 (4) (1995) 44–61.
- 682 [6] M. Priestley, G. MacRae, Seismic tests of precast beam-to-column joint
683 subassemblages with unbonded tendons, PCI Journal 41 (1) (1996) 64–
684 80.
- 685 [7] S. Alcocer, R. Carranza, D. Perez-Navarrete, R. Martinez, Seismic tests
686 of beam-to-column connections in a precast concrete frame, PCI Journal
687 47 (3) (2002) 70–89.
- 688 [8] H. H. Korkmaz, T. Tankut, Performance of a precast concrete beam-to-
689 beam connection subject to reversed cyclic loading, Engineering Struc-
690 tures 27 (9) (2005) 1392 – 1407.
- 691 [9] K. Ong, Z. S. Lin, L. R. Chandra, C. T. Tam, S. D. Pang, Experimental
692 investigation of a DfD moment-resisting beamcolumn connection, Engi-
693 neering Structures 56 (0) (2013) 1676 – 1683.

- 694 [10] H. Parastesh, I. Hajirasouliha, R. Ramezani, A new ductile moment-
695 resisting connection for precast concrete frames in seismic regions: An
696 experimental investigation, *Engineering Structures* 70 (0) (2014) 144 –
697 157.
- 698 [11] P. Negro, D. Bournas, F. Molina, Pseudodynamic tests on a full-scale
699 3-storey precast concrete building: Global response, *Engineering Struc-*
700 *tures* 57 (2013) 594–608.
- 701 [12] D. Bournas, P. Negro, F. Molina, Pseudodynamic tests on a full-scale 3-
702 storey precast concrete building: Behavior of the mechanical connections
703 and floor diaphragms, *Engineering Structures* 57 (2013) 609–627.
- 704 [13] R. Vidjeapriya, K. Jaya, Experimental study on two simple mechanical
705 precast beam-column connections under reverse cyclic loading, *Journal*
706 *of Performance of Constructed Facilities* 27 (4) (2013) 402–414.
- 707 [14] H.-K. Choi, Y.-C. Choi, C.-S. Choi, Development and testing of precast
708 concrete beam-to-column connections, *Engineering Structures* 56 (0)
709 (2013) 1820 – 1835.
- 710 [15] G. Cheok, W. Stone, S. Kunnath, Seismic response of precast concrete
711 frames with hybrid connections, *ACI Structural Journal* 95 (5) (1998)
712 527–538.
- 713 [16] K. Ong, J. Hao, P. Paramasivam, A strut-and-tie model for ultimate
714 loads of precast concrete joints with loop connections in tension, *Con-*
715 *struction and Building Materials* 20 (3) (2006) 169 – 176.

- 716 [17] H.-K. Ryu, Y.-J. Kim, S.-P. Chang, Experimental study on static and
717 fatigue strength of loop joints, *Engineering Structures* 29 (2) (2007) 145
718 – 162.
- 719 [18] H. B. Joergensen, L. C. Hoang, Tests and limit analysis of loop connec-
720 tions between precast concrete elements loaded in tension, *Engineering*
721 *Structures* 52 (2013) 558 – 569.
- 722 [19] A. E. Naaman, J. K. Wight, H. Abdou, SIFCON connections for seismic
723 resistant frames, *Concrete International* 9 (11) (1987) 34–39.
- 724 [20] R. Vasconez, A. Naaman, J. Wight, Behavior of HPFRC connections
725 for precast concrete frames under reversed cyclic loading, *PCI Journal*
726 43 (6) (1998) 58–71.
- 727 [21] L. Maya, C. Zanuy, L. Albajar, C. Lopez, J. Portabella, Experimental
728 assessment of connections for precast concrete frames using ultra high
729 performance fibre reinforced concrete, *Construction and Building Mate-*
730 *rials* 48 (2013) 173 – 186.
- 731 [22] *ACI* Committee 318, Building Code Requirements for Structural Con-
732 crete (ACI 318-08) and Commentary, *ACI*, Farmington Hills, MI (2008).
- 733 [23] A. Bruggeling, G. Huyghe, Prefabrication with concrete, Balkema, Rot-
734 terdam, 1991.
- 735 [24] *fib* International Federation for Structural Concrete Task Group 6.2,
736 Bulletin 43 - Structural connections for precast concrete buildings, *fib*,
737 Lausanne (2008).

- 738 [25] *ACI Innovation Task Group 1, Acceptance Criteria for Moment Frames*
739 *Based on Structural Testing (ACI T1.1-01)*, ACI, Farmington Hills, MI
740 (2001).
- 741 [26] *ACI Innovation Task Group 1, Commentary on Acceptance Criteria*
742 *for Moment Frames Based on Structural Testing (ACI T1.1R-01)*, ACI,
743 Farmington Hills, MI (2001).
- 744 [27] L. Taerwe, A. Van Gysel, Influence of steel fibers on design stress-
745 strain curve for high-strength concrete, *Journal of Engineering Mechan-*
746 *ics* 122 (8) (1996) 695–704.
- 747 [28] R. Neves, J. De Fernandes Almeida, Compressive behaviour of steel fibre
748 reinforced concrete, *Structural Concrete* 6 (1) (2005) 1–8.
- 749 [29] K. Marar, O. Eren, I. Yitmen, Compression specific toughness of nor-
750 mal strength steel fiber reinforced concrete (nssfrc) and high strength
751 steel fiber reinforced concrete (hssfrc), *Materials Research* 14 (2) (2011)
752 239–247.
- 753 [30] *ACI Committee 544, State-of-the-Art Report on Fiber Reinforced Con-*
754 *crete (ACI 544.1R-96)*, ACI, Farmington Hills, MI (1996).
- 755 [31] H.-J. Im, H.-G. Park, T.-S. Eom, Cyclic loading test for reinforced-
756 concrete-emulated beam-column connection of precast concrete moment
757 frame, *ACI Structural Journal* 110 (1) (2013) 115–125.
- 758 [32] O. Ertas, S. Ozden, T. Ozturan, Ductile connections in precast concrete
759 moment resisting frames, *PCI Journal* 51 (3) (2006) 66–76.

- 760 [33] A. Tsonos, Cyclic load behavior of reinforced concrete beam-column
761 subassemblages of modern structures, *ACI Structural Journal* 104 (4)
762 (2007) 468–478.
- 763 [34] L. Massone, J. Wallace, Load-deformation responses of slender rein-
764 forced concrete walls, *ACI Structural Journal* 101 (1) (2004) 103–113.
- 765 [35] CEN, EN 1998-1 - Eurocode 8: Design of structures for earthquake re-
766 sistance - Part 1: General rules, seismic actions and rules for buildingsg,
767 CEN European Committee for Standardization, Brussels, B (2004).
- 768 [36] D. de Lima Arajo, M. C. Curado, P. F. Rodrigues, Loop connection
769 with fibre-reinforced precast concrete components in tension, *Engineer-
770 ing Structures* 72 (2014) 140 – 151.
- 771 [37] D. Hibbitt, B. Karlsson, P. Sorensen, *Abaqus Analysis User’s Manual*,
772 Abaqus, Inc.
- 773 [38] *fib* International Federation for Structural Concrete, *Model Code 2010*,
774 *fib*, Lausanne (2010).
- 775 [39] K. Wille, D. Kim, A. Naaman, Strain-hardening UHP-FRC with low
776 fiber contents, *Materials and Structures* 44 (2011) 583–598.
- 777 [40] M. Yang, C. Huang, J. Wang, Characteristics of stress-strain curve of
778 high strength steel fiber reinforced concrete under uniaxial tension, *Jour-
779 nal of Wuhan University of Technology-Mater. Sci. Ed.* 21 (3) (2006)
780 132–137.